ADDENDUM #3 - MARCH 12, 2024

RE: Coquille School District

Bus Maintenance Building

Project #22.97

FROM: HGE ARCHITECTS, Inc.

333 South 4th Street

Coos Bay, Oregon 97420

541-269-1166

TO: Prospective Bidders

This Addendum forms a part of the Contract Documents and modifies the original Documents dated February 2024, as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

This Addendum consists of **TWO (2)** page(s) together with the following attachments:

None

CHANGES TO PROJECT MANUAL:

- 1. Section 01-2300 Alternates: Paragraph 1.03, A, 1, d: REPLACE with, "Underground electrical service conduit from utility to building and all underslab conduits for electrical, telecommunications, HVAC equipment, and future use by owner. Refer to Sheet E1.1."
- 2. Section 07-4646 Fiber-Cement Siding: Paragraph 2.02, D: DELETE Paragraph D, Drainage Mat. Refer instead to Paragraph B, Furring Strips, Plastic.
- 3. Section 26-2400 Service Entrance, Distribution and Grounding, & Bonding: Paragraph 1.01, B: REPLACE with, "Provide service rated 400-amp meter base with (2) 200-amp service entrance disconnects with associated panels as indicated."

CHANGES TO DRAWINGS:

- **1. Sheets A2.1 A5.1:** REPLACE all mention of "rainscreen mat" with "plastic furring strips". Refer to Section 07-4646 Paragraph 2.02.
- 2. Sheet E1.0 Electrical Symbols & Schedules, Detail 1 1-Line Diagram: In note "(1) 3" EC to utility pole," REPLACE "(1)" with "(2)".

3. Sheet E1.1 Electrical Plan Underslab: In note "Provide (1) 3" PVC underground conduit with pullstring and long-radius sweeps from meter location to utility pole," REPLACE "(1)" with "(2)".

END OF ADDENDUM #3