

ADDENDUM #2 – FEBRUARY 3, 2026

RE: **FIRST BAPTIST CHURCH OF GOLD BEACH**
Building Remodel
Project #25.020

FROM: HGE ARCHITECTS, Inc.
333 South 4th Street
Coos Bay, Oregon 97420
541-269-1166



TO: Prospective Bidders

This Addendum forms a part of the Contract Documents and modifies the original Documents dated January 2026, as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

This Addendum consists of **ONE (1)** page(s) together with the following attachments:

CHANGES TO PROJECT MANUAL:

1. **SECTION 09-6813 Tile Carpeting, Paragraph 2.02 – A.** – REPLACE in entirety with revised paragraph attached.

CHANGES TO DRAWINGS:

1. **Sheet A1.1 DEMO PLAN – Drawing 2**
 - a. Add Note: "CONTRACTOR TO REMOVE (E) FLOORING IN ALL IMPACTED ROOMS"

END OF ADDENDUM #2

**SECTION 09-6813
TILE CARPETING****PART 1 GENERAL****1.01 SECTION INCLUDES**

- A. Carpet tile, fully adhered.
- B. Walk off tile carpeting.

1.02 RELATED REQUIREMENTS

- A. Section 03-3000 - Cast-in-Place Concrete: Restrictions on curing compounds for concrete slabs and floors to receive adhesive-applied flooring.

1.03 REFERENCE STANDARDS

- A. ASTM E648 - Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source; 2014c.
- B. ASTM F710 - Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring; 2011.
- C. CRI 104 - Standard for Installation of Commercial Carpet; 2015.
- D. NFPA 253 - Standard Method of Test for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source; 2015.

1.04 SUBMITTALS

- A. See Section 01-3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on specified products, describing physical and performance characteristics; sizes, patterns, colors available, and method of installation.
- C. Samples: Submit two carpet tiles illustrating color and pattern design for each carpet color selected.
- D. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.
 - 1. See Section 01-6000 - Product Requirements, for additional provisions.
 - 2. Extra Carpet Tiles: Quantity equal to 5 percent of total installed of each color and pattern installed.

PART 2 PRODUCTS**2.01 MANUFACTURERS**

- A. Tile Carpeting :
 - 1. Milliken & Company: www.milliken.com/#sle.
 - 2. J & J Flooring - Textile Composite Flooring.

3. Patcraft - Walkoff Matt Tile (Basis of Design).
4. Substitutions: See Section 01-6000 - Product Requirements.

2.02 MATERIALS

- A. Tile Carpeting (CPT): Tufted, Textured Loop, manufactured in one color dye lot.
 1. Manufacturers:
 - a. Basis of Design: Product Nordic Stories manufactured by Milliken.
 - b. Mohawk
 - c. Patcraft
 2. Tile Size: 19.7 x 50 cm x 50 cm inch, nominal.
 3. Solution dyed.
 4. Tufted Textured Loop.
 5. Gauge: 1/10
 6. Texture Appearance Retention Rating (TARR): Severe.
 7. Critical Radiant Flux: Minimum of 0.22 watts/sq cm, when tested in accordance with ASTM E648 or NFPA 253.
 8. Maximum Electrostatic Charge: 3.5 Kv. at 20 percent relative humidity.
 9. Foot Traffic Recommendation TARR: Heavy.
 10. Soil Release Technology: Sentry Soil Protection. "StainSmart" or manufacturer's integrated stain and soil protection system.
 11. Backing: Standard backing PVC-Free Underscore ES Cushion.
- B. Walk-Off Tile Carpeting (WOT):
 1. Manufacturer:
 - a. Patcraft (Basis of Design)
 - b. Milliken
 - c. J & J
 - d. Substitutions: See Section 01-6000-Product Requirements.
 2. Manufactured in one color dye lot.
 3. Dye method: Solution Dyed.
 4. Tufted yarn weight: 32 oz.

5. Model: Beyond The Door.
6. Size: 24 x 24 inches.
7. Thickness: 205 inch.
8. Density: 8,597.
9. Maximum Electrostatic Charge: 3.5 Kv. at 20 percent relative humidity.
10. Primary Backing Material: Polyester Felt Cushion.
11. Foot Traffic Recommendation TARR: Severe.
12. Adhesive per Manufacturer.

C. Substitutions: Section 01-6000 - Product Requirements.

2.03 ACCESSORIES

- A. Sub-Floor Filler: White premix latex; type recommended by flooring material manufacturer.
- B. Adhesives:
 1. Compatible with materials being adhered; maximum VOC content of 50 g/L; CRI (GLP) certified; in lieu of labeled product, independent test report showing compliance is acceptable.
 2. Recommended by carpet tile manufacturer; releasable type.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that sub-floor surfaces are smooth and flat within tolerances specified for that type of work and are ready to receive carpet tile.
- B. Verify that required floor-mounted utilities are in correct location.

3.02 PREPARATION

- A. Prepare floor substrates as recommended by flooring and adhesive manufacturers.
- B. Remove sub-floor ridges and bumps. Fill minor or local low spots, cracks, joints, holes, and other defects with sub-floor filler.
- C. Apply, trowel, and float filler to achieve smooth, flat, hard surface. Prohibit traffic until filler is cured.
- D. Vacuum clean substrate.

3.03 INSTALLATION

- A. Starting installation constitutes acceptance of sub-floor conditions.

- B. Install carpet tile in accordance with manufacturer's instructions.
- C. Blend carpet from different cartons to ensure minimal variation in color match.
- D. Cut carpet tile clean. Fit carpet tight to intersection with vertical surfaces without gaps.
- E. Installation Method: per Architect
- F. Layout pattern / change of style / color To Be Determined supplied by Architect.
- G. Complete installation of edge strips, concealing exposed edges.

3.04 CLEANING

- A. Remove excess adhesive without damage, from floor, base, and wall surfaces.
- B. Clean and vacuum carpet surfaces.

END OF SECTION